

AD-A156 280


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
GRAFTON POND DAM (NH) (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV NOV 78


1/1

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 280

CONNECTICUT RIVER BASIN
GRAFTON, NEW HAMPSHIRE

GRAFTON POND DAM

NH 00119

NHWRB 96.01

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
JUL 08 1985
S D
G

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

NOVEMBER 1978

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited

DTIC FILE COPY

85 06 13 096

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|--|-----------------------|---|
| 1. REPORT NUMBER NH 00119 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Grafton Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS | | 5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT |
| 7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION | | 6. PERFORMING ORG. REPORT NUMBER |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS | | 8. CONTRACT OR GRANT NUMBER(s) |
| 11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 12. REPORT DATE November 1978 |
| | | 13. NUMBER OF PAGES 54 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Grafton, New Hampshire Tributary to Bicknell Brook | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a gravity concrete structure which about 285 ft. long and has a maximum height of 21 ft. It is intermediate in size with a low hazard potential. The dam is in very poor condition. Deterioration of the dam's two key structural elements, the upstream facing wall and its supporting buttresses, appears to seriously threaten the integrity of the structure. Due to the nature and extent of the deficiencies in this dam, the development of meaningful remedial measures of the dam should be implemented immediately | | |

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:

NEDED

JAN 23 1979

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

I am forwarding to you a copy of the Grafton Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.


A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire 03301, ATTN: Mr. George M. McGee, Sr., Chairman.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely yours,

Incl
As stated


JOHN P. CHANDLER
Colonel, Corps of Engineers
Division Engineer

GRAFTON POND DAM
NH 00119

CONNECTICUT RIVER BASIN
GRAFTON, NEW HAMPSHIRE

| | |
|--------------------|-------------------------------------|
| Accession For | |
| NTIS GRA&I | <input checked="" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| By _____ | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A/ | ✓ ✓ |

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



NATIONAL DAM INSPECTION PROGRAM

PHASE I REPORT

Identification No.: NH 00119
NHWRB No.: 96.01
Name of Dam: GRAFTON POND DAM
Town: Grafton
County and State: Grafton, New Hampshire
Stream: Tributary to Bicknell Brook
Date of Inspection: September 21, 1978

BRIEF ASSESSMENT

The Grafton Pond Dam is an Ambursen dam, a gravity concrete structure named after its designer. The dam is approximately 285 feet long and has a maximum height of 21 feet. Discharges from the reservoir are via a 24 foot wide concrete ogee spillway or two 2 feet wide by 3 feet high steel sluice gates. The dam, which is owned by the New Hampshire Water Resources Board (NHWRB), was built in 1918.

Grafton Pond receives runoff from 3.6 square miles of moderately sloping, heavily forested terrain. The dam's maximum impoundment of approximately 3000 acre-feet places it in the INTERMEDIATE size category, while the lack of any downstream hazard for a considerable distance below the dam results in a LOW hazard potential classification.


Based on the size and hazard potential ratings and in accordance with the Corp's guidelines, the Test Flood (TF) is between the 100 year flood and one half the Probable Maximum Flood (PMF). The selected TF inflow of 1800 cfs results in a discharge at the dam of approximately 900 cfs. Since the discharge capacity of the structure at maximum pond elevation is only approximately 622 cfs, the TF overtops the dam by approximately 0.4 feet.

The Grafton Pond Dam is in VERY POOR condition at the present time. Deterioration of the dam's two key structural elements, the upstream facing wall and its supporting buttresses, appears to seriously threaten the integrity of the structure. For this reason, it is recommended that immediately upon receipt of this report the pond be lowered to at least 7 feet below the spillway crest and that a qualified structural engineer be retained to conduct a detailed inspection and analysis of the dam under fully drawn down conditions.

Until such an inspection can be arranged, it is further recommended that the impoundment be maintained below gage elevation 9.0, or 7 feet below the spillway.

Due to the nature and extent of the deficiencies in this dam, the development of meaningful remedial measures for this structural problem is beyond the scope of this Phase I investigation and should be deferred pending completion of the structural inspection. The only non-structural remedial measure involves the training of local officials in dam operations to decrease response time in operating the dam in the event of an emergency.

The structural investigation recommended above should be accomplished immediately and the dam should remain drawn down until such time as a permanent solution is developed. Based on the dam's VERY POOR condition, periodic inspections should be conducted every 6 months.



William S. Zoino
William S. Zoino
New Hampshire Registration 3226



Nicholas A. Campagna, Jr.
Nicholas A. Campagna, Jr.
California Registration 21006

This Phase I Inspection Report on Grafton Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

Richard F. Doherty

RICHARD F. DOHERTY, MEMBER
Water Control Branch
Engineering Division

Carney M. Terzian

CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division

Joseph A. McElroy

JOSEPH A. MCELROY, CHAIRMAN
Chief, NED Materials Testing Lab.
Foundations & Materials Branch
Engineering Division

APPROVAL RECOMMENDED:

Joe B. Fryar

JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the Test Flood should not be interpreted as necessarily posing a highly inadequate condition. The Test Flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

| | <u>Page</u> |
|--|-------------|
| LETTER OF TRANSMITTAL | |
| BRIEF ASSESSMENT | |
| REVIEW BOARD SIGNATURE SHEET | |
| PREFACE | iv |
| TABLE OF CONTENTS | v |
| OVERVIEW PHOTOS | vii |
| LOCATION MAP | ix |
| SECTION 1 - PROJECT INFORMATION | |
| 1.1 General | 1-1 |
| 1.2 Description of Project | 1-2 |
| 1.3 Pertinent Data | 1-4 |
| SECTION 2 - ENGINEERING DATA | |
| 2.1 Design Records | 2-1 |
| 2.2 Construction Records | 2-1 |
| 2.3 Operational Records | 2-1 |
| 2.4 Evaluation of Data | 2-1 |
| SECTION 3 - VISUAL INSPECTION | |
| 3.1 Findings | 3-1 |
| 3.2 Evaluation | |
| SECTION 4 - OPERATIONAL PROCEDURES | |
| 4.1 Procedures | 4-1 |
| 4.2 Maintenance of Dam | 4-1 |
| 4.3 Maintenance of Operating Facilities | 4-1 |
| 4.4 Description of Any Warning System in Effect | 4-1 |
| 4.5 Evaluation | 4-1 |

Table of Contents - cont.

Page

SECTION 5 - HYDRAULIC/HYDROLOGIC

| | | |
|-----|--|-----|
| 5.1 | Evaluation of Feature | 5-1 |
| 5.2 | Hydraulic/Hydrologic Evaluation | |
| 5.3 | Downstream Dam Failure Hazard Estimate | |

SECTION 6 - STRUCTURAL STABILITY


| | | |
|-----|------------------------------------|-----|
| 6.1 | Evaluation of Structural Stability | 6-1 |
|-----|------------------------------------|-----|

SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

| | | |
|-----|-------------------|-----|
| 7.1 | Dam Assessment | 7-1 |
| 7.2 | Recommendations | 7-1 |
| 7.3 | Remedial Measures | 7-2 |

APPENDICES


| | |
|---|-----|
| APPENDIX A - VISUAL INSPECTION CHECKLIST | A-1 |
| APPENDIX B - FIGURES AND PERTINENT RECORDS | B-1 |
| APPENDIX C - PHOTOGRAPHS | C-1 |
| APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS | D-1 |
| APPENDIX E - INFORMATION AS CONTAINED IN <u>THE NATIONAL INVENTORY OF DAMS</u> | E-1 |




Overview from left abutment showing
bedrock outcrop



Overview from left side downstream
showing spillway



Overview from left side upstream



0 1/2 2 miles
- SCALE -
FROM: USGS MASCOMA, N.H.
QUADRANGLE MAP

GOLDERS, ZOMO, DUBIELL & ASSOC., INC.
GEOTECHNICAL CONSULTANTS
NEWTON UPPER FALLS, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

LOCUS PLAN

GRAFTON POND DAM

NEW HAMPSHIRE

FILE No. 2067

| | |
|-------|-----------|
| SCALE | AS NOTED |
| DATE | SEPT 1978 |

PHASE I INSPECTION REPORT

GRAFTON POND DAM

SECTION 1

PROJECT INFORMATION

1.1 General

(a) Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Goldberg, Zoino, Dunncliff & Associates, Inc. (GZD) has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed was issued to GZD under a letter of August 22, 1978 from Colonel Ralph T. Garver, Corps of Engineers. Contract No. DACW 33-78-C-0303 has been assigned by the Corps of Engineers for this work.

(b) Purpose

(1) Perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests.

(2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-federal dams.

(3) Update, verify and complete the National Inventory of Dams.

(c) Scope

The program provides for the inspection of non-federal dams in the high hazard potential category based upon location of the dams and those dams in the significant hazard potential category believed to represent an immediate danger based on condition of the dam.

1.2 Description of Project

(a) Location

The Grafton Pond Dam lies on a tributary of the Mascoma River approximately 3.3 miles east of Enfield Center, New Hampshire. The dam is reached via an unnamed dirt road off Route 4A, 2.5 miles south of the village. The portion of the USGS Mascoma, NH quadrangle presented on page ix shows this locus. Figure 1 of Appendix B is a site plan developed from the map and the site visit.

(b) Description of Dam and Appurtenances

The dam at the outlet of Grafton Pond is an Ambursen type concrete structure approximately 285 feet long (Page B-4). It consists of a 40 foot end wall on the left bank, 6 adjacent buttress bays with a total length of 75 feet, a spillway crest 24 feet long which spans over two buttress bays, an additional eight buttress bays with a total length of 100 feet and an end wall on the right bank 45 feet long. The left end wall is located on the axis of the dam, while the right wall is splayed approximately 30° in the direction of the reservoir. Twin sluice gates are located within the right bay below the spillway crest (Pages B-4 and B-6).

The front face of this dam slopes on an incline of 45° and varies in thickness from 12 inches at its top elevation to 18 inches at its base (Pages B-5 through B-7). In general, the buttresses supporting the face slab are 14 inches thick, with the exception of the buttresses at either end of the spillway crest and those adjacent to the end walls which are 16 inches thick. The twin steel sluice gates, which are constructed on an incline parallel to the face of the dam, are 2 feet wide and 3 feet high and are equipped with non-rising brass stems and operated with hand wheels. The gates were manufactured by Caldwell and Wilcox Company, Newbury, New Hampshire.

A bridge structure (Page B-4) is located approximately 12 feet downstream of the spillway crest.

(c) Size Classification

The dam's maximum impoundment of 3940 acre-feet falls within the 1000 to 50,000 acre-feet range which defines INTERMEDIATE size category as defined in the "Recommended Guidelines."

(d) Hazard Potential Classification

The lack of any development downstream of the dam for a distance of over 3 miles leads to a LOW hazard potential classification. The only potential damage would be to small bridges on unimproved roads.

(e) Ownership

The NHWRB owns this dam. Key officials are: Chairman George McGee, Chief Engineer Vernon Knowlton, Assistant Chief Engineer Donald Rapoza and Staff Engineer Gary Kerr. The Board's telephone number is (603) 271-3406 and it can also be reached through the State Capitol operator at (603) 271-1110. The NHWRB assumed ownership in 1970 from the Granite State Electric Company, a division of New England Power Company.

(f) Operator

The NHWRB has a permanent operator who visits the dam weekly. All dam operations are directed by the Board. The operator can be contacted through the individuals listed in subparagraph 1.2(e) above.

(g) Purpose of Dam

The dam's primary purpose is to maintain the level of Grafton Pond for recreational use. Some secondary flood control benefits are also derived.

(h) Design and Construction History

The dam was designed and built in 1918 by the Mascoma River Improvement Company as part of an overall hydro-electric development project. The dam has undergone no significant alterations since its construction.

(i) Normal Operational Procedure

The pond is maintained at or slightly above the crest of the spillway during the summer recreational period. In early fall, the Board draws the pond down approximately 8 feet in anticipation of fall storms and spring runoff. The drawdown remains in effect until February, when the pond is allowed to refill to the recreational level.

1.3 Pertinent Data

(a) Drainage Area

Grafton Pond receives runoff from 3.6 square miles of moderately sloping, heavily forested terrain. There is no development around the shores of the pond.

(b) Discharge at Damsite

(1) Outlet Works

The dam's outlet works consist of two 2 feet wide by 3 feet high steel sluice gates equipped with non-rising brass stems and operated by hand wheels. The inverts of the gates are at El. 1223.5.

(2) Maximum known flood at damsite

Records maintained by the NHWRB indicate that the maximum water level since the advent of state ownership was 1.2 feet below the dam crest in December 1973. With both gates open, this pond level would create a discharge of approximately 420 cfs.

(3) Spillway capacity at maximum pool elevation:

370 cfs at El. 1244.5

(4) Gate capacity at normal pool elevation:

233 cfs at El. 1241.5

(5) Gate capacity at maximum pool elevation:

252 cfs at El. 1244.5

(6) Total discharge capacity at maximum pool elevation:

622 cfs at El. 1244.5

(c) Elevation (feet above MSL)

(1) Top of dam: 1244.5

(2) Maximum pool: 1244.5

- (3) Recreational pool: 1241.5
- (4) Spillway crest: 1241.5
- (5) Streambed at centerline of dam: 1223.5
- (6) Maximum tailwater: Unknown

(d) Reservoir

- (1) Length of recreational pool: 1.1 miles ±
- (2) Storage - recreational pool: 3000 acre-feet ±
- maximum pool: 3940 acre-feet ±
- (3) Surface area - recreational pool: 235 acres ±

(e) Dam

- (1) Type: Concrete buttress (Ambursen)
- (2) Length: 285 feet
- (3) Height: 21 feet ±
- (4) Top Width: 2.5 feet ±
- (5) Side slopes - U/S 1:1
- D/S Vertical
- (6) Grout curtain: Unknown
- (7) Cutoff: Plans indicate concrete cutoff at upstream toe

(f) Spillway

- (1) Type: Concrete ogee
- (2) Length of weir: 24 feet
- (3) Crest elevation: 1241.5 ±
- (4) U/S channel: Broad approach from lake
- (5) D/S channel: Narrow, passing under a bridge
12 feet downstream of spillway

(g) Regulating outlets

As mentioned previously, the dam's only regulating outlets are the two steel sluice gates. Subparagraph 1.3(b) presents pertinent data on the gates.

SECTION 2 - ENGINEERING DATA

2.1 Engineering Records

The design of this dam is quite innovative in that it uses a buttress arrangement to eliminate much of the concrete that would normally go into a gravity structure. None of the original design drawings or calculations are available.

2.2 Construction Records

Appendix B contains the construction drawings for the dam. Additionally, the files of the NHWRB contain photographs from 1918 showing the progress of work on the dam. Both sources of information are quite detailed.

2.3 Operational Records

The present owner operates the dam in a manner consistent with its engineering features and intended purpose. Operating records since the advent of state ownership in 1970 are maintained at the Board's Concord office.

2.4 Evaluation

(a) Availability

The available data are quite extensive and therefore warrant a satisfactory evaluation for availability. The lack of design data is not a serious deficiency as the plans are sufficiently detailed to permit backfiguring of engineering data if desired.

(b) Adequacy

The available information is sufficient to permit an evaluation of the dam from the standpoint of reviewing design and construction data. A satisfactory assessment for adequacy is therefore warranted.

(c) Validity

The available construction plans are generally in agreement with the as-built configuration of the dam. Thus, a satisfactory evaluation for validity is assigned.

SECTION 3 - VISUAL OBSERVATIONS

3.1 Findings

(a) General

The Grafton Pond Dam is in VERY POOR condition at the present time. This evaluation is based primarily upon the significant deterioration of the dam's key structural elements, the dam facing wall and its supporting buttresses.

(b) Dam

(1) Left End Wall

Inspection of the left end wall reveals that the top of this wall is severely spalled over 70% of its surface. This spalling can be attributed to moisture intrusion combined with alternating freeze and thaw cycles.

(2) Dam Facing Wall

There is minor surface erosion over the entire facing wall of the structure. This surface erosion can be attributed to ice damage.

The six buttress bays between the left end wall and the spillway and the eight buttress bays between the spillway and the right end wall have expansion joints at alternate bays. These expansion joints consist of steel tee sections embedded in the concrete. The first expansion joint adjacent to the left bank has spalled from the top of the dam to approximately 10 inches below the spillway crest, exposing the steel tee sections. The next expansion joint has similarly spalled from the top of the dam to a point approximately 10 feet lower. The continuation of this joint on the top surface of the dam has opened and spalled. This spalling can also be attributed to moisture intrusion coupled with alternate freeze and thaw cycles. This mode of failure is typical for all expansion joints.

There is spalling at the first expansion joint located adjacent to the right side of the spillway. The concrete has spalled over a distance of approximately 4 feet measured along the sloping face of the structure; the metal expansion tee is exposed and undermined.

The second expansion joint located to the right of the spillway has spalled as deep as the metal tee from the top of the dam to a point some 12 feet down the face of the dam. The third expansion joint has a spall approximately 6 feet long measured from the top of the dam down its face. Again, the steel expansion tee is exposed. The fourth expansion joint has spalled similar to the second.

Surface spalling approximately 4 inches wide by 4 feet long and 1 inch deep has occurred at the top of the facing wall adjacent to the right end wall. This spalling can be attributed to excessive troweling of the concrete and to moisture intrusion coupled with alternate freeze and thaw cycles. There is a horizontal crack on the front face of the wall located in the first buttress bay adjacent to the right abutment. This crack is approximately 1/4 inch wide and extends through the facing wall. The crack is approximately 3 feet below the top of the dam. Approximately 2 feet from the right end wall there is a vertical crack along the facing wall surface.

Investigations of the underside of the facing wall reveal a considerable amount of horizontal cracks, seepage, leaching, stalactites, exudation, and encrustation. In general, the horizontal cracks are located in well defined patterns, suggesting that these cracks occur at the locations of construction joints. The enclosed photographs illustrate the intensity of the facing wall deterioration. Due to the structural hazard condition, no attempt was made to chip away deteriorated concrete for the purpose of investigating the degree of oxidation of the steel reinforcement. However, it can be assumed that oxidation of steel reinforcement does exist.

Construction drawings indicate that the facing wall was designed as a two span section without provision for negative reinforcement over its intermediate support (buttress). Assuming the water surface level is at the spillway crest elevation, preliminary structural calculations reveal that concrete tensile stresses on the exterior of this slab over the intermediate buttress are well beyond its ultimate tensile capacity.

In view of this fact, it can be predicted that vertical cracks have developed in the facing wall (below the water line) over the intermediate supporting buttress. Once cracks develop at these intermediate supports, the facing wall reverts to a simple span structure with open vertical joints as opposed to a two span continuous structure. This situation results in the redistribution of inherent stresses.

Suspected cracking of the facing wall over the intermediate buttresses correlates with observed seepage around the upper surfaces of buttress to slab connections between elevations 1234.5 and 1225.5 (MSL). Furthermore, the construction drawings reveal that a deliberate effort was made to preclude the bonding of the buttresses and facing walls, which suggests a further source for the development of seepage.

Diagonal cracks and spalls are evident at five locations on the back face of the header beams supporting the top of the dam. The first buttress adjacent to the left end wall exhibits diagonal cracks and dislodged concrete. The concrete which has been displaced is triangular in shape and approximately 16 inches on a side. There is additional cracking at the upper end of this buttress and reinforcing steel is exposed. The failures at these locations can be attributed to a lack of restraint against expansion.

(3) Spillway

The spillway crest exhibits a series of longitudinal hairline cracks and minor surface erosion. The hairline cracking can be attributed to over-trowelling the spillway surface in order to obtain a granolithic finish. The minor surface erosion can be attributed to cavitation and to the flow of ice over the spillway. The steel expansion joint adjacent to the left side of the spillway is exposed from its upper terminus downward as far as is visible below the water surface. The erosion at this joint is in excess of 6 inches in width over its exposed length.

The corner of the front facing wall adjacent to the spillway has cracked for a distance of 30 inches above the spillway crest in line with the expansion tee. A block of concrete approximately 18 inches high, 8 inches wide and 12 inches deep has cracked away from the buttress wall adjacent to this particular tee.

(4) Buttresses

Inspection of the buttresses reveals considerable pattern cracking, seepage, erosion, disintegration, scaling, leaching, stalactites, exudation and encrustation. The deteriorated condition of these structural components places the dam in jeopardy. Separate plans locating these deficiencies are included in Appendix B.

The disintegration of concrete at the base of the buttresses is pronounced. In one particular instance, this disintegration is approximately 8 feet in height, 2 feet in width and over 8 inches deep. This deterioration represents a 50% loss in cross section. It is apparent from the visual observations that the exposed surface of the concrete at this particular location is unsound. This condition also exists at the base of the buttress adjacent to the left side of the spillway. Similar types of erosion, but to a lesser degree, are evident in 8 of the remaining 16 buttresses. There is evidence of seepage between all the buttresses and the facing wall. Buttresses Nos. 11, 12, 13 and 14 exhibit only minor seepage, but this continuous flow through the facing wall onto the buttresses over the remaining portion of the structure, though low in terms of volume, is extremely damaging as evidenced by the high degree of erosion. Drain holes were cut through various buttress bases subsequent to construction for the obvious purpose of avoiding ponding adjacent to the buttresses. In general, the erosion of concrete between the buttresses and the facing wall can be attributed to continuous seepage subjected to alternate freeze and thaw cycles. The inventory of the locations of erosion indicates that the highest degree of erosion occurs at the locations of steel expansion joints.

Although erosion at the intermediate buttresses has occurred to a lesser extent, it can be assumed that vertical cracks have occurred in the facing wall over these buttresses below the water line.

The exposed surface of the buttress adjacent to the left side of the spillway has failed structurally. The concrete at this location is badly cracked from 12 inches above to 30 inches above the spillway. The joint between the buttress and the spillway surface has eroded over its entire length. This erosion is approximately 4 inches wide and 2 inches deep. The face of this buttress is also badly checked with a high degree of efflorescence. A triangular concrete section approximately 8 inches on a side and located at the corner of this buttress has been dislodged. There is a conical hole 5 inches deep adjacent to this dislodgement. Expansive forces have also caused the concrete to shear at this location, probably due to lack of reinforcing steel at the connection between the end of the slab and the buttress. Spalls, cracks, checking and efflorescence can be attributed to moisture intrusion coupled with alternate freeze and thaw cycles.

The buttress adjacent to the right side of the spillway exhibits deterioration similar to the left side. This deterioration, which can be attributed to the spalling of concrete over the expansion joint tee, has progressed along the total depth of the concrete facing wall for a distance in excess of 2 feet above the spillway crest. This spalling varies in width from 6 inches at its base to 3 inches at its highest elevation. The connection between the header beam supporting the rear top surface of the facing wall between buttresses exhibits a spall approximately 8 square inches in surface area and 3 inches deep on its face adjacent to the spillway. This spall can be attributed to expansive forces.

(5) Right End Wall

There is a diagonal crack at the top corner of the right end wall immediately adjacent to the first buttress.

This crack, which is approximately 2 feet long, can be attributed to expansive forces. The top of the right end wall exhibits spalling over approximately 10% of its surface area. This spalling can be attributed to moisture intrusion and alternate freeze and thaw cycles. A vertical construction joint located approximately 15 feet from the right buttress has spalled and opened. This spalling can also be attributed to moisture intrusion and alternate freeze and thaw cycles.

(6) Abutments

The left end wall of the dam is in contact with a massive granitic outcrop. The rock appears competent and the widely spaced jointing tightens quickly with depth. There is a small amount of seepage of the junction of the wall with the bedrock outcrop.

The foundation under the right end wall is not visible, but several nearby outcrops suggest that this wall is also founded on competent, granitic material. There is also a small seepage at this abutment.

(7) Foundation Conditions

Observations of the site indicate that the dam is founded on bedrock. This conclusion is consistent with the use of an Ambursen type dam at the site, as this structural system generally requires bedrock support for the buttresses. Photos taken in 1918 and on file with the NHWRB confirm the bedrock foundation and provide an excellent view of the foundation conditions.

(8) Sluice Gates

Inspection of the sluice gates in the presence of a representative of the New Hampshire Water Resources Board indicated that they were extremely difficult to operate. A two-man team attempted to turn the wheels, but was unsuccessful. The inspection team was advised that a 2 by 4 wood fulcrum still required two men and considerable effort to turn this wheel two revolutions, which would raise the gates 1/8 inch.

The bench stands for these sluice gates are located on a plane 45° to that of the floor and parallel to the face of the dam. The left pedestal base exhibits seepage and surface erosion over an area 18 inches square. The right pedestal base also exhibits a minor degree of seepage. The surface erosion can be attributed to moisture intrusion and alternate freeze and thaw cycles.

(9) Downstream Bridge

There is erosion and undermining of the wall extension of the right abutment of the downstream bridge. The eroded area is 6 feet long, 3 feet wide and up to 2 feet deep. This erosion can be attributed to cavitation of the concrete. The left abutment shows no evidence of undermining or erosion.

(c) Appurtenant Structures

The dam has no appurtenant structures.

(d) Reservoir

Examination of the reservoir shore revealed no evidence of instability or potential slides. No sedimentation was noted behind the dam and there was no evidence of work in progress or recently completed which might increase the flow of sediment into the pond. There were no indications of any changes to the surrounding watershed which might adversely affect the runoff characteristics of the basin. There is only one home, located near the right abutment of the dam, within approximately one half mile of the pond.

(e) Downstream Channel

Discharge from the dam passes under a bridge 12 feet downstream and then into a well defined, heavily overgrown channel. There is no development along the channel for at least 3 miles downstream. Some local roads could, however, be affected by a dam failure. There are no downstream conditions which would limit operation of the dam.

3.2 Evaluation

The dam is in VERY POOR condition at the present time and requires immediate corrective action. Fortunately, however, the dam poses only the most remote hazard to downstream life and property.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 Procedures

As mentioned previously, a NHWRB operator visits the dam at least weekly and reports gage readings back to the Concord office. Engineers at the office, in turn, direct any gate operations necessary. The lake is maintained at or slightly above the spillway crest during the summer and is drawn down 8 feet in early fall in anticipation of fall storms and spring runoff.

4.2 Maintenance of Dam

The dam operator inspects the dam during his weekly visits and reports any deficiencies back to the Board's engineers, who take the necessary steps to institute repairs. Additionally, an engineer from the Board inspects the dam annually.

4.3 Maintenance of Operating Facilities

The same procedures outlined above apply to the dam's operating facilities. The gate stems were replaced in the 1971 to 1972 time frame.

4.4 Description of any Warning System in Effect

No formal warning system exists for this dam.

4.5 Evaluation

The present condition of the dam indicates a long period of neglected maintenance. It may, in fact, be too late to arrest further deterioration. As there is no appreciable downstream hazard from a dam failure, the lack of a formal warning system is not a significant problem.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

(a) Available Data

Data sources available for Grafton Pond Dam are "Data on Dams in New Hampshire" and "Data on Reservoirs and Ponds in New Hampshire," both by the New Hampshire Water Control Commission and dated December 6, 1938. These sources contain basic information concerning the dam structure and dimensions. Some of the original hydraulic calculations, which include the maximum waste gate and spillway capacities prior to overtopping of the dam, are also available.

(b) Experience Data

Flood experience data for the dam indicate a maximum water level in the pond of 1.2 feet below the dam crest during a storm in December 1973.

(c) Visual Observations

Grafton Pond Dam is a buttressed concrete structure known as an Ambursen Dam after its designer. The pond and dam are located in Grafton, New Hampshire and discharge into a tributary of Bicknell Brook, which flows towards the village of Lockehaven. The dam has an overall crest length of 285 feet at a height of 3 feet above its spillway. The dam has a maximum height of about 21 feet above the stream bed with a top width of about 2.5 feet.

The discharge works consist of a 24 foot long broad-crested concrete spillway and two 2 foot by 3 foot sluice gates. The gates are operated from a gate house built under the spillway. The elevation of the spillway crest is given in the available data as 1241.5 feet above Mean Sea Level (MSL). The invert elevations of the sluice gates on this basis are therefore at 1223.5 feet. At the time of the inspection the water level in the pond was about four feet below the spillway crest, or at about elevation 1236.5 feet.

Immediately downstream of the dam is a roadway embankment with an 11.0 foot by 11.5 foot bridge opening for the stream. The top of the embankment and bridge are about 4.5 feet lower than the spillway, or at elevation 1237.0.

Although this opening is large enough to pass peak gate and spillway flows, it would very likely be washed away in the event of a dam failure. Beyond this point, the only other structures in the flood hazard area are two other small bridges. No homes or other buildings are located in the region that would be inundated.

(d) Overtopping Potential

The hydrologic conditions of interest in this Phase I investigation are those required to assess the dam's overtopping potential and its ability to safely allow a large flood to pass. This analysis requires use of the storage and discharge characteristics of the structure to evaluate the impact of an appropriately sized Test Flood. The available discharge capacity calculations were used as a check on the calculations developed for this purpose.

Guidelines for establishing a recommended Test Flood based on the size and hazard potential classifications of a dam are specified in the "Recommended Guidelines" of the Corps of Engineers (COE). As shown in these guidelines, the appropriate Test Flood for a dam classified as INTERMEDIATE in size with a LOW hazard potential would be between the 100 year frequency flood and one-half of the Probable Maximum Flood (PMF).

The magnitude of the 100 year peak inflow to Grafton Pond is estimated using a regression relationship provided by the USGS in Water Resources Investigations 78-47, "Progress Report on Hydrologic Investigations of Small Drainage Areas in New Hampshire." This equation, which uses the drainage area, main channel slope and the 24-hour, 2-year frequency precipitation to estimate peak inflow, yields a 100 year peak flood flow of 780 cfs for the Grafton Pond drainage basin.

The chart of "Maximum Probable Peak Flow Rates" obtained from the Corps of Engineers, New England Division is used to determine the PMF. For the 3.6 square mile drainage area above Grafton Pond, which has a hilly topography, the curve for "rolling" terrain gives a PMF flow of 1925 cfs per square mile. This value results in a total PMF of 6,930 cfs, or a one-half PMF flow of 3,470 cfs.

The "Guidelines" further suggest that if a range of values is indicated for the Test Flood, the magnitude most closely related to the involved risk should be selected. Since the risk is towards the lower end of the LOW category, a Test Flood of 1800 cfs is used as inflow to Grafton Pond.

The attenuation of the peak due to storage is estimated using the procedure suggested by the Corps of Engineers, New England Division for "Estimating the Effect of Surge Storage on Maximum Probable Discharges." The Storage-Stage Curve used for these calculations is developed assuming that the surge storage available in a pond is equal to the surface area of the pond times the depth of surge. No spreading or increase in surface area with increasing depth is considered. Use of the recommended procedure shows that the pond storage has a very significant attenuating effect on the magnitude of the peak flow, since the calculations result in a corrected Test Flood flow of about 900 cfs, or a fifty percent reduction in the pond inflow.

The Stage-Discharge Curve is developed by defining discharge as the sum of the flows through the two gates, flow over the spillway, flow over the dam crest, and the flow over the slopes at the ends of the dam. These calculations assume both gates are fully open. Application of the attenuated Test Flood peak discharge of 900 cfs to the derived Stage-Discharge relationship results in a maximum stage at the dam of about 3.4 feet above the spillway, or about 0.4 feet above the dam crest.

5.2 Hydrologic/Hydraulic Evaluation

The results of the hydrologic and hydraulic calculations indicate that the outlet capacity of Grafton Pond Dam is insufficient to pass a Test Flood flow in the lower range of that suggested by the "Guidelines." The maximum capacity of the waste gates and spillway, with the water level at the dam crest, was computed to be 620 cfs. This quantity is in close agreement with the available previous calculation of 684 cfs.

5.3 Downstream Dam Failure Hazard Estimates

The flood hazards in downstream areas resulting from a failure of Grafton Pond Dam are estimated using the procedure suggested in the COE New England Division's "Rule of Thumb Guidelines for Estimating Downstream Dam Failure Hydrographs." This procedure accounts for attenuation of dam failure hydrographs in computing flows and flooding depths for downstream reaches.

For these calculations, failure is assumed to occur as soon as the dam crest is overtopped at an elevation of 1244.5 feet. This level corresponds to a height of 21 feet above the stream bed. For an assumed breach width of 100 feet, the resultant peak discharge due to dam failure is 16,200 cfs.

Downstream of the dam, there are only three structures within the floodway before the confluence with Bicknell Brook. All three are small bridges which are assumed to fail when struck by the dam failure discharge and therefore would not represent significant impediments to the flood wave. No structures are located in the flood hazard area of Bicknell Brook between this confluence and its point of discharge into Mascoma Lake.

Between Grafton Pond and Bicknell Brook, the floodway is divided into two reaches. The first reach is about 3000 feet long with a well defined channel and fairly steep slope. The second reach is 3700 feet long with a somewhat wider channel and shallower slope.

The first reach attenuates the peak from 16,200 cfs to 15,800 cfs. The depth of flow in this reach is 12.3 feet. The second reach further attenuates the flood flow peak to 15,100 cfs and has a depth of flow of 9.8 feet. These flows and depths of flooding would, in all probability, wash out the downstream bridges, but there are no known residences that would be affected. Although the possibility of some bridge and roadway damage is high, the potential for loss of life is considered remote.

SECTION 6 - STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

(a) Visual Observations

The field investigations of the dam revealed no significant displacements, but considerable structural distress which could influence the stability of the structure is evident.

(b) Design and Construction Data

At least one design feature of the dam may have contributed to its present condition and potential instability. The upstream facing slab was designed as a two span structure and contains waterstops at the construction joints on every other buttress. The slab is continuous over intermediate buttresses, but contains, however, no negative reinforcement at these locations. Preliminary calculations within the scope of a Phase I investigation indicate that the slab is stressed beyond its tensile capacity at these intermediate buttresses. Therefore, vertical cracks likely do exist over the buttresses. These cracks, in turn, are not waterproof and have apparently permitted water to penetrate the slab and to induce deterioration of the slab and, in some cases, the supporting buttresses. Additionally, inherent stresses have been redistributed by the slab changing from a two span continuous structure to a single span, simply supported configuration. Section 3 discusses this situation in greater detail.

The construction drawings included in Appendix B are quite detailed and would facilitate the preparation of a stability analysis were one deemed necessary. The operating records maintained since 1970 reveal no evidence of instability under experienced pond levels.

(d) Post-Construction Changes

There have been no significant post-construction changes to the dam.

(e) Seismic Stability

The dam is located in Seismic Zone No. 2 and, in accordance with recommended Phase I guidelines, does not warrant seismic analyses.

SECTION 7 - ASSESSMENT, RECOMMENDATIONS
AND REMEDIAL MEASURES

7.1 Dam Assessment

(a) Condition

The Grafton Pond Dam is in VERY POOR condition at the present time.

(b) Adequacy of Information

Available information is quite extensive and does permit an assessment from the point of view of reviewing design and construction data. This review is a valuable supplement to the visual inspection.

(c) Urgency

The recommendations and remedial measures stated in Paragraphs 7.2 and 7.3 should be initiated within one year of receipt of this report except that the lowering of the pool shall start immediately upon receipt of this report.

(d) Need for Additional Investigation

Additional investigations are required as recommended in Paragraph 7.2.

7.2 Recommendations

It is recommended that a qualified structural engineer be retained to inspect and to analyze the condition of this dam. It is anticipated that such an investigation could result in a recommendation that major repairs be undertaken or that the dam be rebuilt.

7.3 Remedial Measures

Based upon preliminary calculations, it is recommended that the level of Grafton Pond be maintained at a level no higher than gage elevation 9.0 until such time as the reservoir can be completely drawn down to permit the investigation recommended above.

The development of remedial structural measures for this dam, if any exist, is beyond the scope of a Phase I investigation. These measures will more properly result from the investigation recommended above.

The only non-structural remedial measure relates to the dam's operating policy. To decrease response time in the event of an emergency when NHWRB personnel might become over-extended, the Board should train local municipal officials in the proper operation of the dam and establish a procedure for utilizing this manpower resource in the event of unforeseen circumstances.

Technical inspections of the dam should continue to be made every year.

APPENDIX A
VISUAL INSPECTION CHECKLIST

INSPECTION TEAM ORGANIZATION

Date: September 20, 1978

NH 00119
GRAFTON POND DAM
Grafton, New Hampshire
Tributary of Bicknell Brook
NHWRB 96.01

Weather: Sunny and warm

INSPECTION TEAM

| | | |
|-------------------|--|--------------|
| Robert Minutoli | Goldberg, Zoino, Dunnicliff & Associates, Inc. (GZD) | Team Captain |
| William Zoino | GZD | Soils |
| Nicholas Campagna | GZD | Soils |
| Andrew Christo | Andrew Christo Engineers (ACE) | Structural |
| Paul Razgha | ACE | Structural |
| Richard Laramie | Resource Analysis, Inc. | Hydrology |

Mr. Lyle Milligan of the NHWRB accompanied the inspection team and operated the gates.

CHECK LISTS FOR VISUAL INSPECTION

| AREA EVALUATED | BY | CONDITION & REMARKS |
|---|-----------|---|
| SUPERSTRUCTURE | | |
| a. General | | |
| Vertical alignment and movement | <i>EM</i> | No deficiencies noted |
| Horizontal alignment and movement | | No deficiencies noted |
| Condition at abutments | | Base of left abutment in contact with massive granitic outcrop: rock appears to be competent and widely spaced jointing tightens up quickly with depth: bedrock outcrop also evident at right abutment; rock in this area is also granitic with some pegmatite dikes up to a few inches thick |
| Rock slope protection | | Considerable amount of large boulders (up to 2' ø) has been dumped in front of right endwall near abutment; purpose of rock not evident, but presumably for erosion protection; smaller amount at base of left endwall |
| Unusual downstream seepage at abutments | | Small amount of seepage at both abutments |
| Foundation conditions | | Examination of 1918 photos in the records of the NHWRB confirm that the entire structure is founded on bedrock as shown in the plans |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|---------------------------------------|-----------|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| Foundation drainage features | <i>in</i> | None shown on plans or evident at dam |
| b. Left End Wall | <i>PE</i> | |
| General condition of concrete | | Fair |
| Rusting or staining | | None noted |
| Spalling | | Spalling over 70% of its top surface area |
| Erosion or cavitation | | None noted |
| Visible reinforcing | | None noted |
| Seepage or efflorescence | | None noted |
| Cracking | | None noted |
| Junction with dam facing wall | | Minor spalling |
| c. Dam Facing Wall - Impoundment Face | | |
| General condition of concrete | | Poor |
| Rusting or staining | | At expansion joint locations |
| Spalling | <i>TE</i> | Concrete cover above steel expansion joints has spalled and undermined these joints; this condition is evident at all expansion joints; extreme right buttress spalled adjacent to the right end wall |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|---|----|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| Erosion or cavitation | TE | Minor surface erosion |
| Visible reinforcing | | Refer to "Buttress" |
| Seepage or efflorescence | | Refer to "Underside of Facing Wall" |
| Cracking | | Horizontal crack full length of right bay; vertical crack 2 feet from right end wall; for additional cracking refer to "Underside of Facing Wall" |
| d. Buttress Faces Normal to Spillway Axis | | |
| General condition of concrete | | Poor |
| Rusting or staining | | At expansion joint locations |
| Spalling | | Isolated structural failures with related spalls, concrete dislodged |
| Erosion or cavitation | | Joints between buttresses and spillway eroded over entire length |
| Visible reinforcing | | None noted |
| Seepage | | None noted |
| Cracking | TE | Extensive cracking, checking and minor efflorescence |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|---|----|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| e. Buttresses and Under- side of Facing Wall | TC | |
| 1. Buttresses | | |
| General condition of concrete | | Poor - High degree of erosion at connection with facing walls over a major portion of the dam |
| Rusting or stain- ing | | Considerable staining due to seepage |
| Spalling | | Severe |
| Erosion | | Severe |
| Visible reinforcing | | Connection at top of extreme end of left buttress at header beam |
| Seepage or efflour- escence | | Severe - exudation and encrus- tation |
| Scaling | | Severe |
| Cracking | | Severe random cracking |
| 2. Underside of Facing Wall | | |
| General condition of concrete | | Poor - High degree of pattern cracking, seepage, efflour- escence, exudation, encrustation and stalactites |
| Rusting or staining | | Considerable staining due to seepage |
| Spalling | TC | At pattern cracks |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|-----------------------------------|----|--|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| Erosion | TC | At pattern cracks |
| Visible reinforcing | | None noted |
| Seepage | | 2 gpm through longitudinal crack between buttresses Nos. 4 and 5. Seepage in all other buttress bays |
| Efflorescence | | Severe with associated exudation, encrustation and stalactites in all bays |
| Cracking | | Severe pattern cracking in all bays |
| f. Right End Wall | TC | |
| General condition of concrete | | Fair |
| Rusting or staining | | None noted |
| Spalling | | Vertical construction joint spalled, 10% of top surface area spalled |
| Erosion or cavitation | | None noted |
| Visible reinforcing | | None noted |
| Seepage or efflorescence | | None noted |
| Cracking | | Diagonal crack at top corner adjacent to right buttress; vertical construction joint opened |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|-----------------------------------|-----------|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| OUTLET WORKS | | |
| a. Approach Channel | | |
| Bottom conditions | <i>R</i> | Wide, deep approach from pond; bottom not visible |
| Rock slides or falls | | No rock near approach channel |
| Log boom | | None |
| Control of debris | | No debris evident behind dam |
| Trees overhanging channel | <i>R</i> | None |
| b. Spillway | | |
| General condition of concrete | | Fair |
| Rusting or staining | | None noted |
| Spalling | | None noted |
| Erosion or cavitation | | Minor surface erosion |
| Visible reinforcing | | None noted |
| Cracking | | Longitudinal hairline cracks |
| c. Sluice Gates | | The sluice gates are extremely difficult to operate; condition unknown; seepage and surface erosion at base of pedestals; gate house locked |
| d. Downstream Bridge Structure | | |
| General condition | | Fair |
| Right abutment | <i>TJ</i> | Wall extension severely eroded |


| CHECK LISTS FOR VISUAL INSPECTION | | |
|--|----|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| Left abutment | TC | Good condition |
| e. Existence of gage | TC | On upstream face near spillway; spillway crest at 16.0 on gage |
| OUTLET CHANNEL (immediate area) | | |
| Slope conditions | | Discharge flows directly under bridge and into a well defined channel moderately steep slopes |
| Rock slides or falls | | None noted |
| Control of debris | | Some debris downstream which may have washed over dam |
| Trees overhanging channel | | None between dam and bridge |
| Other obstructions | | None noted |
| RESERVOIR | | |
| a. Shoreline | | |
| Evidence of slides | | None noted |
| Potential for slides | | Shoreline stable |
| b. Sedimentation | | None noted |
| c. Upstream hazard areas in the event of back-flooding | | No development along shore of pond |
| d. Changes in nature of watershed (agriculture, logging, construction, etc.) | TC | None noted |

| CHECK LISTS FOR VISUAL INSPECTION | | |
|-----------------------------------|----|---|
| AREA EVALUATED | BY | CONDITION & REMARKS |
| DOWNSTREAM CHANNEL | | |
| Restraints on dam operation | ✓ | None noted |
| Potential flooded area | | Only small road bridges on unimproved roads subject to flooding |
| OPERATION & MAINTENANCE FEATURES | | |
| a. Reservoir regulation plan | | |
| Normal procedures | | Maintain water at spillway level during summer recreational period; draw down 8 feet in late summer or early fall for flood control |
| Emergency procedures | | Permanent dam tender could open gates fully, but response time might be slow due to large number of dams to be covered |
| Compliance with designated plan | | Satisfactory |
| b. Maintenance | ✓ | Present condition of dam points to inadequate maintenance effort |

APPENDIX B

| | <u>Page</u> |
|---|-------------|
| FIGURE 1 Site plan | B-2 |
| Plan and elevation of dam showing locations of cracks and spalls in header beam and spalls at bases of buttress | B-3 |
| Plan and elevation of dam showing locations of cracks and seepage through slab | B-4 |
| Deck and crest details showing locations of typical deficiencies | B-5 |
| Details of sluice gate bay | B-6 |
| Bulkhead (buttress) details | B-7 |
| List of pertinent records not included and their location | B-8 |

Note: Pages B-3 through B-5 are Mascoma River Improvement Company drawings dated 1916 modified by GZD to reflect current deficiencies



GOLDBERG, ZOINO, DUNNCLIFF & ASSOC., INC.
 GEOTECHNICAL CONSULTANTS
 NEWTON UPPER FALLS, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND
 CORPS OF ENGINEERS
 WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

FIG. 1
 SITE PLAN

FILE No. 2067

GRAFTON POND DAM

NEW HAMPSHIRE

SCALE 1" = 100'

DATE SEPT 1978

10-11-19

SPAS

11

SPRING BRACK

CHARTERED

COAST GUARD BOAT AT HEAD OF BEAM.

10

உயர்வுகூட்டுதல்

(1)
11
x
1
1
1
1

[illegible]

166

三

○

1

10

100

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

0
1
2
3

11

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

100

NOTES DRAWING HAS BEEN REDUCED
SIZES ARE NOT AS SHOWN

U.S. DEPARTMENT OF JUSTICE

100

100

100

Ch. 11


44
C-6897

100

1000

C-687.

C-687.



70
60
50
40
30
20
10

CRACKS AND SEEPAGE THROUGH SLAB


MINOR BUTTERFLIES -
GIZMAGUE

NOTE: DRAWING HAS BEEN REDUCED
SCALES ARE NOT AS SHOWN

SEE PAGE THROUGH SLAB AT BUTRESS WALLS


GENERAL PLAN AND ELEVATION
AMBERSEN DAM
GRANTON POND - MASCUMA RIVER

FILE NO. 3-391
250-1-2245




NOTE: DRAWING HAS BEEN REDUCED
SCALES ARE NOT AS SHOWN

| | |
|--|----|
| DICK AND CREST DETAILS AMBUSEN DAM CRAFTON FORD - MASCOMA RIVER MASCOMA RIVER PROJECT N. 100° 00' 00" W. 1/4 SECTION 36, T. 100 N., R. 100 W. | |
| FILE NO. 50351 MAP NO. F-2217 | 85 |



NOTE: DRAWING HAS BEEN REDUCED
 SCALES ARE NOT AS SHOWN



| | |
|------------------------------------|--|
| PROJECT HEAD DETAILS | |
| AMERICAN DAM | |
| GRAFTON POND - MASSACHUSETTS RIVER | |
| DESIGNED BY: [illegible] | |
| CHECKED BY: [illegible] | |
| DATE: [illegible] | |
| SCALE: [illegible] | |
| SHEET NO. 1 OF 1 | |

C 685

The New Hampshire Water Resources Board, 37 Pleasant Street, Concord, NH 03301 maintains a comprehensive correspondence file on the dam dating back to the 1930's. Included in this file are:

- (a) Several pages of calculations done by the NHWRB in 1978 for a possible resurfacing of the dam.
- (b) One page of calculations done by the NHWRB in 1939 concerning the discharge capacity of the dam.
- (c) A 1939 report by the New Hampshire Water Control Commission entitled "Data on Reservoirs and Ponds in New Hampshire."
- (d) A 1939 report by the same agency entitled "Data on Dams in New Hampshire."
- (e) Operational records since the advent of state ownership in 1970.
- (f) Photos from 1918 showing the construction of the dam at various phases.

APPENDIX C
SELECTED PHOTOGRAPHS



1. View from downstream of deteriorated concrete at junction of buttress and face of dam



2. View from downstream of deteriorated concrete and efflorescence at junction of buttress and face of dam



3. View from downstream of seepage through dam
at junction of buttress and face of dam




4. View from top of dam showing deteriorated
condition of construction joints in face
of dam




5. View from downstream showing deterioration and structural failure of concrete at junction of top of dam and buttress



6. View from spillway showing cracking, spalling and efflorescing of concrete



7. View from spillway showing severe erosion of concrete wall immediately downstream of outlet



8. Detail of Photo 7 showing water flowing through corner of downstream wall and road bridge abutment

APPENDIX D
HYDROLOGIC/HYDRAULIC COMPUTATIONS

Grafton Pond Dam

Size classification (f(storage)) = Intermediate

Hazard classification = Low

Therefore the appropriate Test Flood is between the 100-yr freq. flood and one-half the PMF

To determine the 100-yr frequency flood the following regression equation is used (LeBlond, USGS Water Resources Investigations 78-47):

$$P_{100} = 0.55 A^{1.05} S^{0.56} I^{2.72}$$

where A = drainage area (mi^2)

S = main channel slope (ft/mi)

I = max. 24-hr precip 80 yr. recur. (in.)

$A = 3.6 \text{ sq. mi.}$

$S = \frac{220 \text{ ft}}{.7 \text{ mi}} = 310 \text{ ft}/\text{mi}$

$I = 2.7 \text{ in}$

$$P_{100} = 0.55 (3.6)^{1.05} (310)^{0.56} (2.7)^{2.72}$$

$$P_{100} = 782 \text{ cfs}$$

The PMF for this basin, with rolling topography and a drainage area of 3.6 mi^2 is

$$\text{PMF} = (1925 \text{ cfs}/\text{mi}^2)(3.6 \text{ mi}^2) = 6930 \text{ cfs}$$


Grafton Pond Dam



If the PMF is .6930 cfs then $\frac{1}{4}$ the PMF is 3465 cfs
which means:

$$782 \text{ cfs} < \text{Test Flood} < 3465 \text{ cfs}$$

To reflect the associated hazard (middle-low) the
Test Flood is chosen to be:

$$\text{Test Flood} = 1800 \text{ cfs}$$



equivalent damFlow

Q_1 = sluice gate flow (two 3'x2' gates)

Q_2 = spillway flow (width 23.75')

Q_3 = dam crest flow (width 261.25')

Q_4 = flow over side slopes (slope = 3:1)

Q_5 = flow over side slopes (slope = 10:1)

Assume $h=0$ at the spillway crest; for all the follow calculations the water level is assumed to be at the spillway crest. This is to check the dams overtopping potential with the worst prior conditions.

for $h < 0$

$$Q_1 = 0.57 (12.0 \text{ ft}^2) \sqrt{2(32.2)(h+18)} \quad \text{with both gates open}$$

$$Q_2 = Q_3 = Q_4 = Q_5 = 0$$

for $0 < h < 3.0'$

$$Q_1 = 0.57 (12.0 \text{ ft}^2) \sqrt{2(32.2)(h+18)}$$

$$Q_2 = 3.0 (23.75') h^{3/2}$$

$$Q_3 = Q_4 = Q_5 = 0$$

for $h > 3.0'$

$$Q_1 = 0.57 (12) \sqrt{2(32.2)(h+18.0)}$$

$$Q_2 = 3.0 (23.75) h^{3/2}$$

$$Q_3 = 3.0 (261.25) (h-3.0)^{3/2}$$

$$Q_4 = 2.8 (5(h-3.0)) (0.5(h-3.0))^{3/2}$$

$$Q_5 = 2.8 (10(h-3.0)) (0.5(h-3.0))^{3/2}$$

The listing of an output from a program to calculate the head-discharge relationship follow.

The maximum capacity of the sluice gates and the spillway before overtopping is 622 cfs from the computer output. The data has this flow calculated to be 684 cfs a 9% difference. The computer results are more conservative

1. Underflow sluice gate equation, Rouse Engineering Hydraulics, p. 60

60

```

100 REMARK: DISCHARGE CALCULATION FOR GRAFTON POND - GATE OPEN
110 PAGE
120 E=1.5
130 PRINT FROM GRAFTON POND - GATE OPEN"
140 PRINT USING 150: "DISCHARGE FROM GRAFTON POND - GATE OPEN"
150 IMAGE / 2T"HEAD"30T"DISCHARGE"
160 PRINT USING 170:
170 IMAGE 1T"(FEET)"32T"(CFS)"
180 PRINT USING 190:
190 IMAGE 10T"TOTAL
200 REMARK: Q7 is flow over the side slopes, Q3 is flow over the
210 REMARK: dam crest, Q2 is flow over the spillway, and Q1 is flow
220 REMARK: through the gate.
230 FOR H=0 TO 13.5 STEP 0.5
240 Q1=0.57*12*(2*32.2*(H+18))↑0.5
250 Q2=3*23.75*H↑E
260 Q3=0
270 Q4=0
280 Q5=0
290 IF H<=3 THEN 320
300 Q4=2.8*(5*(H-3))*(0.5*(H-3))↑E
305 Q5=2.8*(10*(H-3))*(0.5*(H-3))↑E
310 Q3=3*261.25*(H-3)↑E
320 Q7=Q4+Q5
330 Q6=Q1+Q2+Q3+Q7
340 PRINT USING 350:H,Q6,Q1,Q2,Q3,Q7
350 IMAGE 1T,2D,2D,9D,8D,10D,11D,13D
360 NEXT H
370 END

```

DISCHARGE FROM GRAFTON POND - GATE OPEN

| HEAD (FEET) | TOTAL | GATES | DISCHARGE (CFS) SPILLWAY | DAM CREST | SIDE SLOPES |
|----------------|-------|-------|--------------------------------|-----------|-------------|
| 0.00 | 233 | 233 | 0 | 0 | 0 |
| 0.50 | 261 | 236 | 25 | 0 | 0 |
| 1.00 | 311 | 239 | 71 | 0 | 0 |
| 1.50 | 373 | 242 | 131 | 0 | 0 |
| 2.00 | 447 | 245 | 202 | 0 | 0 |
| 2.50 | 530 | 249 | 282 | 0 | 0 |
| 3.00 | 622 | 252 | 370 | 0 | 0 |
| 3.50 | 1001 | 255 | 467 | 277 | 3 |
| 4.00 | 1626 | 257 | 570 | 784 | 15 |
| 4.50 | 2421 | 260 | 680 | 1440 | 41 |
| 5.00 | 3361 | 263 | 797 | 2217 | 84 |
| 5.50 | 4430 | 266 | 919 | 3098 | 147 |
| 6.00 | 5620 | 269 | 1047 | 4072 | 231 |
| 6.50 | 6925 | 272 | 1181 | 5132 | 340 |
| 7.00 | 8339 | 274 | 1320 | 6270 | 475 |
| 7.50 | 9860 | 277 | 1463 | 7482 | 638 |
| 8.00 | 11485 | 280 | 1612 | 8763 | 830 |
| 8.50 | 13211 | 283 | 1766 | 10109 | 1053 |
| 9.00 | 15037 | 285 | 1924 | 11519 | 1309 |
| 9.50 | 16962 | 288 | 2086 | 12988 | 1600 |
| 10.00 | 18984 | 290 | 2253 | 14515 | 1925 |
| 10.50 | 21103 | 293 | 2424 | 16098 | 2287 |
| 11.00 | 23317 | 296 | 2599 | 17734 | 2688 |
| 11.50 | 25627 | 298 | 2779 | 19423 | 3128 |
| 12.00 | 28032 | 301 | 2962 | 21161 | 3608 |
| 12.50 | 30532 | 303 | 3149 | 22949 | 4131 |
| 13.00 | 33125 | 306 | 3340 | 24784 | 4696 |
| 13.50 | 35813 | 308 | 3534 | 26666 | 5305 |

Job 148


Dam 664

RTH

11/13/78

8 of 17

Grafton Pond Dam



D-9

Grafton Pond


Storage - Stage Relationship:

Surface Area of Pond at normal elevation = 231 acres
= 0.361 mi²

1" of runoff yields $\rightarrow \frac{1" (3.6 \text{ mi}^2 (640 \text{ ac/sg. mi}))}{231 \text{ acres}}$

$\rightarrow 9.974"$ rise in water surface

1' of rise results from $\frac{12}{9.974} = 1.20"$ of runoff.




Job 148

Dan Safety

RTH

11/13/78

10 of 17



D-11

Grafton Pond

Reduction in Flow due to Storage:

Assume total storm volume = 8"

Then use COE suggested methodology with additional iterations:

$$Q_{P_2} = Q_{P_1} \left(1 - \frac{\text{STORI}}{18}\right)$$

$$\textcircled{1} \quad Q_{P_1} = 1800 \text{ cfs} \rightarrow H_1 = 4.11 \text{ feet}$$

$$H_1 = 4.11 \text{ feet yields} \rightarrow 4.11(1.20) = 4.93 \text{ inches surcharge storage}$$

$$\therefore Q_{P_2} = 1800 \left(1 - \frac{4.93}{8}\right) = 690.5 \text{ cfs}$$

$$\textcircled{2} \quad Q_{P_2} = 690.5 \text{ cfs} \rightarrow H_1 = 3.09 \text{ ft}$$

$$H_1 = 3.09 \text{ feet yields} \rightarrow 3.09(1.20) = 3.71 \text{ inches surcharge storage}$$

$$\therefore Q_{P_3} = 1800 \left(1 - \frac{3.71}{8}\right) = 965.6 \text{ cfs}$$

$$\textcircled{3} \quad Q_{P_3} = 965.5 \text{ cfs} \rightarrow H_1 = 3.45 \text{ feet}$$

$$3.45 \text{ ft yields} \rightarrow 3.45(1.20) = 4.14 \text{ inches surcharge storage}$$

$$\therefore Q_{P_4} = 1800 \left(1 - \frac{4.14}{8}\right) = 868.5 \text{ cfs}$$

$$\textcircled{4} \quad Q_{P_4} = 868.5 \text{ cfs} \rightarrow H_1 = 3.33 \text{ feet}$$

$$3.33 \text{ ft yield} \rightarrow 3.33(1.20) = 3.99 \text{ inches surcharge storage}$$

$$\therefore Q_{P_5} = 1800 \left(1 - \frac{3.99}{8}\right) = 902.2 \text{ cfs}$$

$$\textcircled{5} \quad Q_{P_5} = 902.5 \text{ cfs} \rightarrow H_1 = 3.37 \text{ feet}$$

$$3.37 \text{ feet} \rightarrow \text{yield } 3.37(1.20) = 4.04 \text{ inches surcharge}$$

$$\textcircled{6} \quad \text{Final } Q_P \rightarrow \text{avg surcharge storage} = (4.04 + 3.99)/2 = 4.02 \text{ in}$$

$$\therefore Q_{P_5} = 1800 \left(1 - \frac{4.02}{8}\right) = 896.2 \text{ cfs}$$

$$\text{So } H = \underline{3.36 \text{ feet}} \rightarrow \text{dam overtopped by } \underline{0.36 \text{ feet}}$$

Grafton Pond

Calculation of Estimated Downstream Dam Failure Flood Stages - Based on COE "Rule of Thumb" Guidelines, April 1978.

Step 1: Reservoir Storage at Time of Failure

First assume the failure occurs when the dam is overtopped (USGS elev. = 1244.5')

$$\text{Storage} = \text{Normal} + \text{Surcharge} = 2300 + (3)(231) = \underline{2993 \text{ Ac-ft}}$$

Step 2: Peak Failure Atflow

$$Q_p = 8/27 W_b \sqrt{g} Y_0^{3/2}$$

$$W_b = \text{breach width} < 40\% \text{ width} = 114.0'$$

$$W_b = 100'$$

$$Y_0 = \text{depth of dam} = 1244.5 - 1223.5 = 21.0'$$

$$Q_p = 8/27 (100) \sqrt{32.2} (21)^{3/2}$$

$$= \underline{16,180 \text{ cfs}}$$

Step 3: Develop Stage - Discharge Routing for Downstream Reaches

(Cross-sections from USGS topo maps and field data)

There are very few structures downstream; just three bridges. These bridges are small and are assumed to fail when and if the dam fails. The downstream floodway from Grafton Pond Dam is divided into two Reaches. These reaches are shown on the following page.


Grafton Pond

Reach 1: From Dam to where slope changes

$L = 3000'$

$n = 0.04$

$S = \frac{1223.5 - 1140}{3000'} = 0.028$




Reach 2: From first reach to Bicknell Brook


$L = 3700'$

$n = 0.04$

$S = \frac{1140 - 1090}{3500} = 0.014$



The following pages contain computer output tables of Stage - Discharge Relationships as well as a map showing the two reaches.



| DEPTH | ELEV | AREA | WPER | HYD-R | AR2/3 | Q |
|-------|------|--------|-------|-------|--------|---------|
| 0.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 |
| 1.0 | 0.5 | 5.3 | 11.0 | 0.5 | 3.1 | 19.5 |
| 1.5 | 1.0 | 17.0 | 12.0 | 0.5 | 5.9 | 61.2 |
| 2.0 | 1.5 | 24.0 | 14.0 | 1.2 | 19.6 | 122.9 |
| 2.5 | 2.0 | 31.0 | 15.0 | 1.5 | 31.5 | 198.5 |
| 3.0 | 2.5 | 39.0 | 17.0 | 2.0 | 46.2 | 291.0 |
| 3.5 | 3.0 | 47.0 | 18.0 | 2.5 | 64.1 | 400.5 |
| 4.0 | 3.5 | 56.0 | 19.0 | 3.0 | 84.1 | 524.0 |
| 4.5 | 4.0 | 67.0 | 21.0 | 3.5 | 106.6 | 664.8 |
| 5.0 | 4.5 | 84.0 | 31.0 | 4.0 | 112.5 | 701.5 |
| 5.5 | 5.0 | 105.0 | 41.0 | 5.0 | 134.5 | 839.2 |
| 6.0 | 5.5 | 132.0 | 51.0 | 6.0 | 170.3 | 1061.4 |
| 6.5 | 6.0 | 163.0 | 61.0 | 7.0 | 219.7 | 1369.2 |
| 7.0 | 6.5 | 204.0 | 71.0 | 8.0 | 283.3 | 1768.6 |
| 7.5 | 7.0 | 241.0 | 81.0 | 9.0 | 363.6 | 2266.4 |
| 8.0 | 7.5 | 289.0 | 91.0 | 10.0 | 460.3 | 2872.1 |
| 8.5 | 8.0 | 339.0 | 101.0 | 11.0 | 576.4 | 3594.2 |
| 9.0 | 8.5 | 396.0 | 111.0 | 12.0 | 712.4 | 4440.8 |
| 9.5 | 9.0 | 457.0 | 121.0 | 13.0 | 869.9 | 5418.2 |
| 10.0 | 9.5 | 524.0 | 131.0 | 14.0 | 1048.4 | 6538.1 |
| 10.5 | 10.0 | 595.0 | 141.0 | 15.0 | 1252.0 | 7806.3 |
| 11.0 | 10.5 | 672.0 | 152.0 | 16.0 | 1480.6 | 9230.3 |
| 11.5 | 11.0 | 753.0 | 162.0 | 17.0 | 1735.9 | 10818.4 |
| 12.0 | 11.5 | 840.0 | 172.0 | 18.0 | 2017.8 | 12577.7 |
| 12.5 | 12.0 | 931.0 | 182.0 | 19.0 | 2328.5 | 14515.0 |
| 13.0 | 12.5 | 1028.0 | 192.0 | 20.0 | 2669.0 | 16639.1 |
| 13.5 | 13.0 | 1129.0 | 202.0 | 21.0 | 3041.0 | 18955.6 |
| 14.0 | 13.5 | 1236.0 | 212.0 | 22.0 | 3444.6 | 21470.3 |
| | | | | | 3881.2 | 24192.3 |

GRAFTON POND REACH ONE

| DEPTH | ELEV | AREA | WPER | HYD-R | AR2/3 | Q |
|-------|------|--------|-------|-------|---------|---------|
| 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 0.5 | 0.5 | 10.3 | 21.4 | 0.5 | 6.3 | 27.5 |
| 1.0 | 1.0 | 21.0 | 22.4 | 0.5 | 19.0 | 171.9 |
| 1.5 | 1.5 | 32.0 | 24.5 | 1.1 | 39.0 | 277.9 |
| 2.0 | 2.0 | 44.0 | 27.1 | 1.2 | 63.1 | 403.8 |
| 2.5 | 2.5 | 56.0 | 28.5 | 2.2 | 91.6 | 548.7 |
| 3.0 | 3.0 | 69.0 | 29.5 | 2.3 | 124.5 | 712.0 |
| 3.5 | 3.5 | 82.0 | 31.9 | 3.1 | 161.5 | 893.3 |
| 4.0 | 4.0 | 96.0 | 35.5 | 1.7 | 202.7 | 754.6 |
| 4.5 | 4.5 | 119.0 | 39.5 | 1.5 | 171.2 | 938.4 |
| 5.0 | 5.0 | 162.0 | 47.2 | 1.5 | 212.9 | 1314.9 |
| 5.5 | 5.5 | 224.0 | 55.8 | 1.6 | 298.3 | 1885.3 |
| 6.0 | 6.0 | 306.0 | 64.4 | 1.8 | 427.0 | 2671.4 |
| 6.5 | 6.5 | 407.0 | 73.4 | 2.0 | 606.1 | 3697.4 |
| 7.0 | 7.0 | 527.0 | 81.6 | 2.4 | 838.9 | 4989.5 |
| 7.5 | 7.5 | 666.0 | 91.2 | 2.6 | 1132.1 | 6573.0 |
| 8.0 | 8.0 | 825.0 | 101.6 | 2.9 | 1491.3 | 8472.4 |
| 8.5 | 8.5 | 1003.0 | 117.4 | 3.6 | 1922.3 | 10711.5 |
| 9.0 | 9.0 | 1201.0 | 138.4 | 3.9 | 2430.6 | 13313.7 |
| 9.5 | 9.5 | 1417.0 | 156.1 | 4.1 | 3020.4 | 16300.0 |
| 10.0 | 10.0 | 1653.0 | 173.3 | 4.5 | 3698.5 | 19695.0 |
| 10.5 | 10.5 | 1908.0 | 193.9 | 5.0 | 4468.0 | 23517.7 |
| 11.0 | 11.0 | 2183.0 | 211.5 | 5.8 | 5335.9 | 27789.6 |
| 11.5 | 11.5 | 2477.0 | 249.1 | 6.1 | 6305.8 | 32530.8 |
| 12.0 | 12.0 | 2790.0 | 287.7 | 6.3 | 7380.6 | 37761.4 |
| 12.5 | 12.5 | 3122.0 | 326.3 | 6.8 | 8567.7 | 43500.6 |
| 13.0 | 13.0 | 3474.0 | 365.0 | 7.5 | 9869.7 | 49767.7 |
| 13.5 | 13.5 | 3845.0 | 403.6 | 8.0 | 11291.7 | 56581.4 |
| 14.0 | 14.0 | 4236.0 | 443.6 | 8.5 | 12837.6 | |

GRAFTON POND REACH TWO

Grafton Pond

Step 4: Calculate Downstream Attenuation

Reach 1 - $Q_{P1} = 16180 \text{ cfs} \rightarrow h_1 = 12.39 \text{ feet}$
 $A_1 = 911.72 \text{ ft}^2$

$$V_{11} = \frac{(3000' \times 911.72 \text{ ft}^2)}{43560} = 62.79 \text{ Ac-ft}$$

$$Q_{P2T} = 16180 \left(1 - \frac{62.79}{2993}\right) = 15840 \text{ cfs}$$

$15840 \text{ cfs} \rightarrow h_2 = 12.31 \text{ ft}$
 $A_2 = 897.10 \text{ ft}^2$

$$V_2 = \frac{3000(897.1)}{43560} = 61.78$$

$$V_{AVG} = \frac{62.79 + 61.78}{2} = 62.28 \text{ Ac-ft}$$

$$Q_{PAVG} = 16180 \left(1 - \frac{62.28}{2993}\right) = 15843 \text{ cfs} \rightarrow h_2 = 12.31 \text{ ft}$$

Reach 2 - $Q_{P1} = 15843 \text{ cfs} \rightarrow h_1 = 9.92 \text{ ft}$
 $A_1 = 1617.5 \text{ ft}^2$

$$V_1 = \frac{3700(1617.5)}{43560} = 137.4 \text{ Ac-ft}$$

$$Q_{P2T} = 15843 \left(1 - \frac{137.4}{2993}\right) = 15116 \text{ cfs}$$

$15116 \text{ cfs} \rightarrow h_2 = 9.80 \text{ ft}$
 $A_2 = 1560.0 \text{ ft}^2$

$$V_2 = \frac{3700(1560)}{43560} = 132.5 \text{ Ac-ft}$$

$$V_{AVG} = \frac{137.4 + 132.5}{2} = 135.0 \text{ Ac-ft}$$

$$Q_{Pa} = 15843 \left(1 - \frac{135.0}{2993}\right) = 15128 \text{ cfs} \rightarrow h = 9.80 \text{ ft}$$

| <u>Reach</u> | <u>Stage</u> | <u>Discharge to downstream</u> |
|--------------|--------------|--------------------------------|
| 1 | 12.31 ft | 15843 cfs |
| 2 | 9.80 ft | 15128 cfs |

APPENDIX E
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

INVENTORY OF DAMS IN THE UNITED STATES

| | | | | | | | | | |
|-------|-----------------|--------|------|------------------|------------------|------------------|-----------------|-----|----|
| STATE | IDENTITY NUMBER | COUNTY | CITY | NAME | LATITUDE (NORTH) | LONGITUDE (WEST) | REPORT DATE DAY | MO | YR |
| NH | 11915 | | | GRAFTON POND DAM | 4334.8 | 7202.7 | 27 | NOV | 78 |

| | |
|--------------|---------------------|
| POPULAR NAME | NAME OF IMPOUNDMENT |
| | GRAFTON POND |

| | | |
|--------------------------------------|---------------------|------------|
| NEAREST DOWNSTREAM CITY-TOWN-VILLAGE | DIST FROM DAM (MI.) | POPULATION |
| LOCKHAVEN | 4 | 150 |

| | | | |
|----------------|----------|------------------------|---------------------------------|
| YEAR COMPLETED | PURPOSES | STRUCTURAL HEIGHT (FT) | IMPOUNDING CAPACITIES (ACRE-FT) |
| 1918 | RC | 21 | 3000 |

DIST OWN FED R PRV/FED SCS A VEN/DATE
N N N N 13DEC78

REMARKS

23-CONCRETE ARMORSEN TYPE 23-FORMERLY HYDROELECTRIC STORAGE

| | | | | | | | | | | | | |
|----------|-------------------------|--------------------|---------------------|-----------|----------|-----|-------------|------------|------------|-------------|------------|------------|
| SPILLWAY | MAXIMUM DISCHARGE (CFS) | VOLUME OF DAM (CY) | POWER CAPACITY (MW) | INSTALLED | PROPOSED | NO. | LENGTH (FT) | WIDTH (FT) | DEPTH (FT) | LENGTH (FT) | WIDTH (FT) | DEPTH (FT) |
| 235 | 24 | 370 | | | | | | | | | | |

| | | |
|-------------------------|-------------------------|-------------------------|
| OWNER | ENGINEERING BY | CONSTRUCTION BY |
| MASCOMA RIVER IMPROV CO | MASCOMA RIVER IMPROV CO | MASCOMA RIVER IMPROV CO |

| | | | |
|-------------------|--------------|-----------|-------------|
| REGULATORY AGENCY | CONSTRUCTION | OPERATION | MAINTENANCE |
| | NONE | NONE | NONE |

| | | | | |
|-------------------------|---------------------|-----|----|--------------------------|
| INSPECTION BY | INSPECTION DATE DAY | MO | YR | AUTHORITY FOR INSPECTION |
| JOHN DUNNICLIFF + ASSOC | 20 | SEP | 78 | PUBLIC LAW 92-367 |

REMARKS

FORMERLY GRANITE STATE ELECTRIC CO

END

FILMED

8-85

DTIC